

Addendum 1: Invitation for Bids for 2027 Rehabilitation Project at the Incline Railway

Please see below for responses to questions from potential bidders:

1. Will RWP be required for this work? No.
2. Please verify all materials are to be new. That is correct, all materials are to be new.
3. Please verify 24" spacing for all trestle ties on project. Yes.
4. Will trestle ties be marked prior to work commencing? Yes.
5. Can you provide dimensions and measurements for the Upper Station Passing Switch Plan? This is unable to be verified and measured prior to bid time. There are ~90 ft. of 4 running rails from the upper station to the passing switch point. Contractor is to measure and document dimensions and geometry prior to rail removal. Pay item includes reconstruction of existing switch configuration, rail blocking, guard rail, and any OTM. Running rail is paid separately.
6. What working windows can the Contractor expect to work? Shutdown dates are from January 2 to February 28.
7. Please confirm that rail is to be jointed and not welded since welding is included in the specifications. Rail is to be jointed.

Annie Powell

Annie Powell, Director of Grants & Procurement, 8.5.26